



Phone: (701) 280-0187
Fax: (701) 280-9021

**Moorhead Area Public Schools Improvements
Probstfield Elementary School Addition
Moorhead, MN**

**Project No. 13-040
Date: April 7, 2014**

BID DATE & TIME: Thursday, April 10, 2014 at 2:00 pm

ADDENDUM NUMBER 3

**The following additions, clarifications, deletions and/or changes shall be made to the
SPECIFICATIONS:**

Section 00 0109 – Bid Package Summary

1. Add the following clarifications to the Bid Package Summary under 31A-Earthwork, 32B-Landscaping, 32C-Paving and Surfacing and 33-Site Utilities.

Bid Package 31A- Earthwork

1. Stripping of black dirt to 10 feet outside the foundation walls.
2. Excavation of footings and foundation walls.
3. Furnish and install granular fill to 4" below finish floor. Coordinate the placement of final 6" with Concrete Contractor.
4. Back fill with clay under any sidewalks within 10 foot outside the foundation walls.
5. Backfill and rough grade all other areas 10 feet outside of foundation walls.
6. Haul excess black dirt from site.
7. Staking and grading necessary to complete this work.
8. Foundation will be staked by 3A-Concrete.
9. Tracking pad as required to complete this work.
10. Demolition as shown on the drawings.
11. Silt fence, inlet protection and Soil Erosion permit to complete the work on the site.
12. Sweep streets as required during this contractors work.

Bid Package 32B Landscaping

1. Finish grading of all landscaping
2. Furnish and install all plants and. seeding as specified and shown on the drawings.
3. Protection of seeded areas as outlined in Section 32 9219.3.06.A and Section 329249.3.06.B by Addendum Number 2.

Bid Package 32C Paving and Surfacing

1. Stripping and furnish and install required fill, embankment, aggregate base, geotextile fabric and other materials to complete the work as per the grading plan.
2. Rough grading of all lawn and playground areas.
3. Backfill of curb and gutter.
4. All sub-grade preparation to complete paving and surfacing and sidewalk work.

5. Staking and grading to complete this work.
6. All concrete sidewalks up to new foundation wall, curb and gutter, valley gutter, aprons etc. as shown on the plans.
7. Sweeping of streets as required during this contractors work.
8. Sweeping of lots prior to striping of parking lot.
9. Parking lot Striping as shown on the plans.
10. Storm water permit necessary to complete this work.

Bid Package 33-Site Utilities

1. Stripping and demolition of items to complete the site utility work.
2. Staking and grading work to complete site utility work.
3. Excavation and backfill to complete this work.
4. Rough grading of black dirt to complete this work.
5. All materials and labor to complete the installation of the site utility work.
6. Stub sanitary and storm sewer 5 feet into the building footprint.
7. Temporary patch at street and sidewalk areas until paving contractor can permanently patch the areas.
8. Sub-grade prep and Granular base under all sidewalks.

The following additions, deletions and/or changes shall be made to the DRAWINGS:

Drawing A3.4 - Roof Plan

1. Roof Types: Change roof type 2 to include 6 inches continuous thickness of polyisocyanurate roof insulation in lieu of 4 inches.

**The following materials and/or equipment have been accepted as APPROVED EQUALS:
(Note: see Electrical and Mechanical portion of Addendum for additional approved equals).**

Section	Specified Product	Approved Equal
08 7100 - Door Hardware	2.60 Exit Devices Von Duprin	Precision Hardware
08 7100 - Door Hardware	2.10 Closers A. LCN 4011/4111EDA	Stanley Commercial QDC100

END OF ADDENDUM NUMBER 3