



Phone: (701) 280-0187
Fax: (701) 280-9021

**Moorhead Area Public Schools Improvements
Probstfield Elementary School Addition
Moorhead, MN**

**Project No. 13-040
Date: April 7, 2014**

BID DATE & TIME: Thursday, April 10, 2014 at 2:00 pm

ADDENDUM NUMBER 4

AFFECTS BID PACKAGES 31A – EARTHWORK, 32C – PAVING & SURFACING, & 33 – SITE UTILITIES

The following additions, clarifications, deletions and/or changes shall be made to the SPECIFICATIONS:

Bid Package 31A - Earthwork

1. Stripping and furnish and install required fill, embankment, aggregate base, geotextile fabric and other materials to complete the work as per the grading plan to complete work for entire site.
2. Excavation of footings and foundation walls
3. Furnish and install granular fill to 4" below finish floor. Coordinate the placement of final 6" with Concrete Contractor.
4. Back fill with clay under any sidewalks within 10 foot outside the foundation walls
5. Backfill and rough grade all lawn and playground areas. Lawn areas shall receive a minimum of 6" of black dirt.
6. Haul excess black dirt from site.
7. Staking and grading necessary to complete this work.
8. Tracking pad as required to complete this work
9. Sweeping of streets as required during this contractors work
10. Demolition as shown on the drawings.
11. Silt fence, inlet protection and Soil Erosion permit to complete the work on the site.
12. Sweep streets as required during this contractors work.

Bid Package 32C - Paving and Surfacing

1. Backfill of curb and gutter.
2. Touch up and dress sub-grade to complete paving and surfacing and sidewalk work.
3. All granular cushion sand as detailed under sidewalks.
4. All concrete sidewalks up to new foundation wall, curb and gutter, valley gutter, aprons etc. as shown on the plans
5. Sweeping of streets as required during this contractors work.
6. Sweeping of lots prior to striping of parking lot.
7. Parking lot Striping as shown on the plans.

Bid Package 33 - Site Utilities

1. Stripping and demolition of curb, gutter, sidewalk etc. to complete the site utility work
2. Staking and grading work to complete site utility work
3. Excavation and backfill to complete this work
4. Rough grading of black dirt to complete this work.
5. All materials and labor to complete the installation of the site utility work.
6. Stub sanitary and storm sewer 5 feet into the building footprint
7. Temporary patch at street and sidewalk areas until paving contractor can permanently patch the areas.
8. Sub-grade prep and Granular base under all sidewalks

END OF ADDENDUM NUMBER 4